



ROBERTS
CIVIL ENGINEERING

301 Sea Island Road Suite 10, St. Simons Island, GA 31522
912-638-9681 Office

October 26, 2020

Owner: Brantley County Board of Commissioners
33 Allen Road
Nahunta, GA 31553

Re: Brantley County 2018-2020 LMIG Projects- Little Buffalo Creek, Bid No. 375

Addendum No. 2

Questions and Responses from Pre-Bid Conference:

- Q1: Will the County provide fill dirt?
R1: Yes, Brantley County will provide fill dirt, but the contractor will be required to excavate and haul it from the borrow pit. The borrow pit location is approximately 7 miles away from Little Buffalo Creek Road at: SMYRNA LANDFILL, Smyrna Church Rd., Nahunta, GA 31553
- Q2: Is the contractor in charge of removing mailboxes that are currently in the ROW?
R2: No, Brantley County will remove and relocate mailboxes and fences currently in the ROW.
- Q3: Who is responsible for coordinating with the power company regarding clearing?
R3: The contractor will be responsible for coordinating with Utility companies for needed clearing limits.
- Q4: Item #8 with DOT Ref. #400 of the Bid Sheet shows 2" *Asphalt Surface Course 12.5mm Superpave* and the Construction Details on sheet 13 of the Site Construction Plans say 1.5" *Asphalt Surface Course Type F*. Which is the correct thickness?
R4: The correct thickness of Asphalt Surface Course is 1.5" which will also change the quantity to 1,054 tons. (See attached revised Bid Sheet)

Changes to Site Construction Plans:

1. Triple Surface Treatment detail on sheet 13 included 6" *Soil Cement (45 LB/SY)* and has been replaced with 6" *Crushed Limerock or Aggregate Base Compacted to 100% Modified Proctor.*

Changes to Construction Site Plans for 8'x 8' Box Culvert with Wingwalls:

1. Stockpile quantity on sheet 4 read *12,816 C.Y.* and has changed to *12,816 C.F.*

Changes to Bid Sheet:

1. Item #8 with DOT Ref. #400 has been changed from *2" Asphalt Surface Course 12.5mm Superpave* with a quantity of *1,400 TN* to *1.5" Asphalt Surface Course 12.5mm Superpave* with a quantity of *1,054 TN*.
2. Line Item Numbers 26-28 have been added to the Bid Sheet as follows:

Line Item No.	DOT Ref. No.	Item Description	Qty	Unit	Unit Price	Amount
26.	641	Guardrail	200	LF		
27.	550	18" Reinforced Concrete Pipe Cross Drain	32	LF		
28.	550	18" Flared End Section	2	EA		

Technical Contact:
Jeff Bors
Project Manager
912-638-9681
jborgs@robertscivilengineering.com